

**Tabela robót ziemnych droga woj. nr 671
od km 35+300 do km 36+127**

Kilometr	Hektometr	Powierzchnia		Średnia powierzchnia		Odległość	Objętość		Suma algebraiczna		
		wykop	+	nasyp	-		wykop	+	nasyp	+	-
		m ²		m ²			mb	m ³		m ³	
35+	300,00	1,250		0,480							
					1,225	0,900	25,00	30,63	22,50		
35+	325,00	1,200		1,320						8,125	
					1,080	1,540	7,97	8,61	12,27		
35+	332,97	0,960		1,760						4,459	
					0,735	2,170	17,03	12,52	36,96		
35+	350,00	0,510		2,580						-19,98	
					0,260	3,525	25,00	6,50	88,13		
35+	375,00	0,010		4,470						-101,60	
					0,090	4,235	25,00	2,25	105,88		
35+	400,00	0,170		4,000						-205,23	
					0,475	3,510	25,00	11,88	87,75		
35+	425,00	0,780		3,020						-281,10	
					0,515	3,540	13,97	7,19	49,45		
35+	438,97	0,250		4,060						-323,36	
					0,735	2,755	11,03	8,11	30,39		
35+	450,00	1,220		1,450						-345,64	
					0,730	1,540	25,00	18,25	38,50		
35+	475,00	0,240		1,630						-365,89	
					0,160	1,215	25,00	4,00	30,38		
35+	500,00	0,080		0,800						-392,27	
					0,140	1,040	25,00	3,50	26,00		
35+	525,00	0,200		1,280						-414,77	
					0,250	1,255	25,00	6,25	31,38		
35+	550,00	0,300		1,230						-439,89	
					0,300	1,120	4,18	1,25	4,68		
35+	554,18	0,300		1,010						-443,32	
					0,280	1,105	20,82	5,83	23,01		
35+	575,00	0,260		1,200						-460,50	
					0,425	1,230	13,82	5,87	17,00		
35+	588,82	0,590		1,260						-471,62	
					0,420	1,330	11,18	4,70	14,87		
35+	600,00	0,250		1,400						-481,80	
					0,410	1,505	25,00	10,25	37,63		
35+	625,00	0,570		1,610						-509,17	
					0,705	1,615	25,00	17,63	40,38		
35+	650,00	0,840		1,620						-531,92	
					0,675	1,735	25,00	16,88	43,38		
35+	675,00	0,510		1,850						-558,42	
					0,525	1,810	25,00	13,13	45,25		
35+	700,00	0,540		1,770						-590,55	
					0,415	1,910	25,00	10,38	47,75		
35+	725,00	0,290		2,050						-627,92	
					0,325	2,025	25,00	8,13	50,63		
35+	750,00	0,360		2,000						-670,42	
					0,365	1,915	25,00	9,13	47,88		
35+	775,00	0,370		1,830						-709,17	
					0,505	1,595	25,00	12,63	39,88		
35+	800,00	0,640		1,360						-736,42	
					0,610	1,205	25,00	15,25	30,13		
35+	825,00	0,580		1,050						-751,30	
					0,570	1,355	25,00	14,25	33,88		
35+	850,00	0,560		1,660						-770,92	
					0,525	1,350	25,00	13,13	33,75		
35+	875,00	0,490		1,040						-791,55	
					0,425	1,360	25,00	10,63	34,00		
35+	900,00	0,360		1,680						-814,92	

**Tabela robót ziemnych droga woj. nr 671
od km 35+300 do km 36+127**

Załącznik Nr 1

Kilometr	Hektometr	Powierzchnia		Średnia powierzchnia		Odległość	Objętość		Suma algebraiczna			
		wykop	+	nasyp	-		wykop	+	nasyp	+	-	
		m ²		m ²			mb		m ³		m ³	
						0,235	1,735	25,00	5,88	43,38		
35+	925,00	0,110	1,790	0,055	1,710	25,00	1,38	42,75			-852,42	
35+	950,00		1,630	0,125	1,410	25,00	3,13	35,25			-893,80	
35+	975,00	0,250	1,190	0,190	1,230	25,00	4,75	30,75			-925,92	
36+	0,00	0,130	1,270	0,070	2,555	6,12	0,43	15,64			-951,92	
36+	6,12	0,010	3,840	0,005	5,105	13,88	0,07	70,86			-967,13	
36+	20,00	0,000	6,370	0,010	4,880	5,00	0,05	24,40			-1037,92	
36+	25,00	0,020	3,390	0,080	2,855	25,00	2,00	71,38			-1062,27	
36+	50,00	0,140	2,320	0,700	1,860	25,00	17,50	46,50			-1131,64	
36+	75,00	1,260	1,400	1,345	1,200	25,00	33,63	30,00			-1160,64	
36+	100,00	1,430	1,000	2,305	0,825	25,00	57,63	20,63			-1157,02	
36+	125,00	3,180	0,650	3,400	0,580	2,00	6,80	1,16			-1120,02	
36+	127,00	3,620	0,510								-1114,38	
				0,560	1,933	827,00	421,93	1536,31				