

Odcinek drogi Nr 671
"wyrównanie podbudowy kruszywem"
w km 34+900 - 36+127

Załącznik Nr 2

Kilometr	Hektometr	Powierzchnia		Średnia powierzchnia		Odległość	Objętość		Zużycie na miejscu	Nadmiar objętości		Suma algebraiczna	
		wykop +	nasyp	wykop +	nasyp -		wykop +	nasyp -		wykop +	nasyp -	+	-
		m ²		m ²			mb	m ³		m ³	m ³		m ³
35	300,00		0,000										
	325,00		2,130		1,455	25,00		36,38			36,38		-36,38
	332,97		2,910		3,215	7,97		25,62			25,62		-62,00
	350,00		4,300		3,605	17,03		61,39			61,39		-123,39
	375,00		4,720		4,510	25,00		112,75			112,75		-236,14
	400,00		4,610		4,665	25,00		116,63			116,63		-352,77
	425,00		2,810		3,710	25,00		92,75			92,75		-445,52
	438,97		0,820		1,815	13,97		25,36			25,36		-470,87
	450,00		0,890		0,855	11,03		9,431			9,43		-480,30
	475,00		1,460		1,175	25,00		29,375			29,38		-509,68
	500,00		0,590		1,025	25,00		25,625			25,63		-535,30
	525,00		1,030		0,810	25,00		20,250			20,25		-555,55
	550,00		1,280		1,155	25,00		28,875			28,88		-584,43
	554,18		1,380		1,330	4,18		5,559			5,56		-589,99
	575,00		0,950		1,165	20,82		24,255			24,26		-614,24
	588,82		1,000		0,975	13,82		13,475			13,475		-627,72
	600,00		0,900		0,950	11,18		10,621			10,621		-638,338
	625,00		1,500		1,200	25,00		30,000			30,000		-668,338
	650,00		1,870		1,685	25,00		42,125			42,125		-710,463
	675,00		2,070		1,970	25,00		49,250			49,250		-759,713
	700,00		1,710		1,890	25,00		47,250			47,250		-806,963
					1 580	25 00		39 500			39 500		

Odcinek drogi Nr 671
"wyrównanie podbudowy kruszywem"
w km 34+900 - 36+127

Załącznik Nr 2

	725,00		1,450		1,385	25,00		34,625		34,625		-846,463
	750,00		1,320		1,225	25,00		30,625		30,625		-881,088
	775,00		1,130		0,900	25,00		22,500		22,500		-911,713
	800,00		0,670		0,845	25,00		21,125		21,125		-934,213
	825,00		1,020		1,095	25,00		27,375		27,375		-955,338
	850,00		1,170		1,130	25,00		28,250		28,250		-982,713
	875,00		1,090		0,970	25,00		24,250		24,250		-1010,963
	900,00		0,850		1,115	25,00		27,875		27,875		-1035,213
	925,00		1,380		1,230	25,00		30,750		30,750		-1063,088
	950,00		1,080		0,540	25,00		13,500		13,500		-1093,838
	975,00		0,000		0,320	25,00		8,000		8,000		-1107,338
36	0,00		0,640		0,625	6,12		3,825		3,825		-1115,338
	6,12		0,610		0,660	13,88		9,161		9,161		-1119,163
	20,00		0,710		0,835	5,00		4,175		4,175		-1128,324
	25,00		0,960		1,025	25,00		25,625		25,625		-1132,499
	50,00		1,090		1,310	25,00		32,750		32,750		-1158,124
	75,00		1,530		0,975	25,00		24,375		24,375		-1190,874
	100,00		0,420		0,290	25,00		7,250		7,250		-1215,249
	125,00		0,160		0,155	2,00		0,310		0,310		-1222,499
	127,00		0,150		0,075							-1222,809
												-1222,809
						827,0		1222,8		1222,8		